



# FONT HILL STREAM RESTORATION – CENTENNIAL LANE WEST

DESIGN BUILD STREAM RESTORATION PROJECT

PUBLIC MEETING - NOVEMBER 30, 2017



# Agenda

---

- Welcome and Introductions
- Project Background
- Proposed Design
- Construction Process
- Schedule
- Question and Answer Session





# Location Map



# Welcome and Introductions

---



**Brian Cleary, PE**  
*Project Manager, Howard County*



**Frank Bubczyk**  
*Stream Restoration Designer, JMT*



**Rick Scaffidi**  
*Stream Restoration Contractor, EQR*





# Environmental Quality Resources

---

- Since 1991 – 26 years, 26 crews
- Hundreds of miles stream restoration
- Over 5,000 acres wetland mitigation
- Over 3,000,000 native trees planted



# Johnson, Mirmiran & Thompson

- Since 1971 – 45 years, 1,400 professionals
- Over 80 Water Resources & Environmental Specialists
- Designer of the Upper Little Patuxent (ULP) Design-Build Stream Restoration





# Why is Stream Restoration Needed?

---

## Improve Ecology

- Plant Trees, Remove Invasive Species
- Pollinators, Birds, and Other Wildlife

## Chesapeake Bay TMDL

- Reduce Sediment and Nutrient Pollution

## Flooding

- Lower or Maintain 100-year Floodplain Elevation
- Reduce Flood Velocity Improve Ecology












# Why is Stream Restoration Needed?



# Past Impacts




Mill Density 1840 US Census  
~65,000 Water-powered Mills

- Glacial Limits
- Pre-Wisconsin
  - Wisconsin
- Mills per 100 sq-km (# counties)
- 0.0 - 2.1 (299)
  - 2.1 - 4.8 (258)
  - 4.8 - 8.8 (170)
  - 8.8 - 23.6 (108)
  - 23.6 - 61.2 (1)

*"There is no neighborhood in any part of the United States without a water gristmill." Thomas Jefferson, 1786*

Walter and Merritts compilation, 2008, *Science*  
Map and GIS database by M. Rahnis



Lidar analysis (15 cm vertical resolution), from Merritts, Walter, and Rahnis





# Past Impacts


---

Few (if any) local, unimpacted systems remaining





# The Evidence






# Why is Stream Restoration Needed?






# Proposed Design





# Proposed Design



- Elimination of Point Sourced Sediments
- Re-establishment of Wetland Root Zone
- Wetland Enhancement/Creation
- Increased Hydraulic Recharge
- Hyporheic Connection

- Repurposing of Renewable Resources
- In stream facet restoration and habitat
- Thermal buffering
- Carbon Sequestering
- Substrate Restoration

- Stability to 100-year event
- Increased Flow Attenuation
- Floodplain & Channel Diversity
- Significant Nutrient Reductions
- Aesthetic and Educational Value





# Restoration?

- Reduce the amount of imported / unnatural materials
- Reduced costs – quarry shortages
- Ease of construction
- Least carbon emissions and climate-resilient design of the approaches, focusing on restoration with native geology



After



**Approx. \$1.5 million restoration**





# Upper Little Patuxent Stream Restoration

---



# Upper Little Patuxent Stream Restoration

---





# Proposed Design





# Construction Process



*Access*

DATE: 08/11/11  
PROJECT: FONT HILL TRIBUTARY STREAM RESTORATION  
SECTION: CENTRAL LANE WEST  
DRAWN BY: J. W. HARRIS  
CHECKED BY: J. W. HARRIS





# Construction Process

---

## What to Expect:

- Safe and efficient construction process
- Work starting at Centennial Lane
- Process is phased to minimize disturbance and time in each section
- Significant buffer remains between the residents and construction operation
- Site is kept clean, and follows all local, state, and federal regulations





# Construction Process

---

Project: Nash Run

Construction  
Equipment





# Construction Process

---

Project: Dead Run

Stabilize active channel  
at the end of each day





# Construction Process

---

Project: Nash Run

Minimize noise,  
vibration, and dust





# Construction Process

---

Project: Scotts Level Branch

Typical Construction  
Hours: 7 a.m. – 5 p.m.  
weekdays





# Construction Process

---

Project: Goose Creek

Tree removal and  
replanting





# Project Schedule

---

Item	Timeframe
Public Comment Period	Now - December 15, 2017
Next Design Milestone	March 2018
Next Public Meeting	Spring/Summer 2018
Construction	September 2018





# Questions?

---





# Contact Us

---



Brian F. Cleary  
DPW Stormwater Management Division  
(410) 313-6455  
[bcleary@howardcountymd.gov](mailto:bcleary@howardcountymd.gov)

<https://www.howardcountymd.gov/Departments/Public-Works/Bureau-Of-Environmental-Services/Stormwater-Management>

